7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate estimate of quantities of work required for restoring Belluti tank, Registered No. 33, Sidlaghatta taluk.

Items of work.	*Per.*	*Quantity.*
Bund 56·00—		
Earthwork	C. yds.	* 13,064
Turfing	S. yds.	9,066
B. M. and registered No. stones	L. S.	Rs. 6
Grade stones	No.	40
Old stone work	C. yds.	461
New stone work (laterite)	„	1,976
Sluices No. 1 and 2—		
Cutting bund	L. S.	Rs. 80
Earthwork excavation	C. yds.	28
Burnt brick in surki mortar	C. ft.	1,262
Do stone slabs	S. ft.	432
Cutting orifice stone with rod and plug, &c.	L. S.	Rs. 20
Chunam plastering	Sqrs.	12·48
Guage stone	L. S.	Rs. 30
Waste weir 150′ long—		
Earthwork	C. yds.	363
Brick in surki mortar	C. ft.	1,968
Plastering, rough	Sqrs.	10·07
Do nice	„	11·05
Slabs	S. ft.	619
Rough stone work, sujicut	C. yds.	432
Do stone wing wall	„	18

* Earthwork will be done by raiyats.

N. ARUNACHELLAM MUDALIAR, *Exec. Engineer.*

HESSARGHATTA WATER-SUPPLY DIVISION.

Notice, dated 29th May 1899.

It is hereby notified that the undermentioned individuals are called upon to present themselves before the undersigned within one month from this date, to receive payment of the balance deposit tendered by them for house-connection, &c., noted against each. If they or their legal representatives fail to receive payment within the above mentioned time, the same will be credited to Government.

Names.	Amount. Rs. a. p.
Mr. Vencoba Rao	3 2 7
Venkataramanappa	2 9 9
Batcha Mudaliar	9 3 6
H. Bassappa	4 15 10
S. K. Nanjundappa	7 4 11
B. Puttiah	3 1 11
Chiksankappa	5 12 5
Chitambro Savojee	4 5 5
H. Nanjundappa	13 3 9
M. Ranganna	12 4 2
Rukmini Boyee	11 12 7
Nanjundsastri	1 0 4
B. Krishna Setty	11 11 6
Syed Mahomed	12 14 2
Bheemasen Rao	13 9 6
Muniyappa	16 13 10

V. RANGASAWMY IYENGAR, *Exec. Engr.*